

PRETERMINATED CABLES



Browse on Mobile

 Browse on Web

NEXCONEC[®] Copper Pre-Terminated trunk assemblies are the perfect solution for Enterprise / Premise & Data Centre applications where speed of installation is important. Factory termination and testing simplify installation, saving time and labor as compared to field terminated installations.

Custom-made configurations in pre-engineered lengths with connectors to meet the specific needs of each application. Assemblies are typically built with a choice of 6, 8, 12 or 24 cable bundle using LSZH or PVC jacket. Standards compliant premium connectors and cable are used to ensure the best possible headroom and performance.

FEATURES

- ✓ Conform to IEC, EIA-TIA performance requirements
- ✓ Factory tested using Fluke tester
- ✓ Available in Cat5E, Cat6 and Cat6A
- ✓ Custom cable and fan-out length
- ✓ High performance and reliability
- ✓ Cost saving and rapid development
- ✓ Cable jacket available in LSZH, CM and PVC, and CPR Certified cables

APPLICATIONS

- ✓ Enterprise / Premise networks
- ✓ Direct Connection to Equipment or patch panel
- ✓ High Performance and Reliability - 100% tested
- ✓ Data Center networks

ORDER INFORMATION

Ask Sales for Order Details: sales@nexconec.com

Or [Contact Us](#) by filling website contact form, one of our colleagues will get back to you shortly!